**** IF PROPOSAL IS ACCEPTED IT WILL BECOME PART OF THE CONTRACT ****

BRIGHTLINE ELECTRIC LLC (sample, fictional company)

Date: 10/27/2026
Attention: Estimating Dept.
Project: Riverside Clinic Tenant Improvment, 4,800 SF

We are pleased to submit our proposal for the Electrcial scope as follows. Price valid 30 days.

BASE BID	1	LS	$186,400.00
		Total	$186,400.00

SCOPE OF WORK

All labor and material per electrical drawings E0.1-E4.2 dated 9/30/26. Electrical permit and inspection fees. New 400A panelboards LP-1 and LP-2 and 75 kVA dry-type transformer. Branch circuit wiring, receptacles and devices. Light fixtures furnished and installed per fixture schedule. Lighting controls and occupancy sensors per plans. Emergency and exit lighting. Mechanical equipment connections; VFDs furnished by mechanical, installed and wired by Brightline. Fire alarm system design, permit and installation, including devices and panel. Low voltage rough-in: boxes, conduit stubbed above ceiling with pull string. Grounding and bonding per NEC. Cleanup of our own debris to GC dumpster. Shop drawings and submittals. One-year warranty on labor and material.

EXCLUSIONS

1. Temporay power and lighting (by GC)
2. Utility co. charges, fees, or aid to construction
3. Data / telecom cabling & terminations
4. Security, access control, CCTV
5. Fire caulking / firestoping
6. Cutting, patching & painting
7. Roof penetrations and flashing
8. Trenching, excavation, backfill
9. Concrete pads, housekeeping pads, encasement
10. Overtime or off-hours work
11. Bond (add 1.5% if required)
12. Arc flash / short circuit / coordination study
13. Owner furnished equipment connections not shown on E-sheets
14. Seismic bracing / engineering
15. Access panels
16. Any work not specifically listed above

ALTERNATE 1: Add EV charger rough-in for 4 stalls ..... ADD $9,800.00

Thank you for the opportunity. Please call with any questions.
Brightline Electric LLC

APPROVED BY: _____ DATE: _____